

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-21212-00-00
Spot: NWNWSESW Sec/Twnshp/Rge: 30-2S-41W
1100 feet from S Section Line, 1500 feet from W Section Line
Lease Name: MYERS UNIT Well #: 2-30
County: CHEYENNE Total Vertical Depth: 5145 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5138		275 SX
SURF	8.625	429		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/29/2015 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 269-7290

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/10 sx of 1000# gel and 500 # hulls.
8 5/8" surface casing set at 429' w/400 sx cement. 5 1/2" production casing set at 5138' w/275 sx cement. TD 5145'. PBTD 5070' w/CIBP.
Perforations: 4639' - 4656', 4842' - 4847' and 5085' - 5089'. Well depleted.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/29/2015 3:05 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 3645' and 2910'. Ran tubing to 4596. Pumped 10 sx gel followed by 75 sx cement w/200 # hulls. Pulled tubing to 3631' and pumped 25 sx cement w/25 # hulls. Pulled tubing to 2892' and pumped 140 sx cement w/150 # hulls. Pulled tubing to 1446' and pumped 120 sx cement w/75 # hulls. Circulated cement to surface. Pulled tubing to surface. Connected to 5 1/2" casing and pumped 25 sx cement. Connected to 8 5/8" surface casing and pumped 60 sx cement. Plug complete.

GPS: 39.84644N -101.96909W

Perfs:

Top	Bot	Thru	Comments
5085	5089		CHER LM
4842	4847		LKC 'K'
4639	4656		LKC 'D'

Remarks: SWIFT SERVICES TICKET # 28161

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

KCC WICHITA

CM

FEB 13 2015

RECEIVED

2/18/15 CKM