

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-19157-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 28-14S-13W
1015 feet from S Section Line, 4053 feet from E Section Line
Lease Name: COLLIVER A Well #: 20
County: RUSSELL Total Vertical Depth: 2930 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2929		225 SX
SURF	8.625	679		375 SX

Well Type: EOR UIC Docket No: E05781.7 Date/Time to Plug: 01/29/2015 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/8 sx gel.
CIBP at 2800'

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/29/2015 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1350' and 340'. Ran tubing to 2730' and pumped 8 sx gel followed by 50 sx cement. Pulled tubing to 1400' and pumped 100 sx cement. Pulled tubing to 400' and pumped 40 sx cement. Cement circulated. POOH. Hooked up to casing and pumped 40 sx cement to circulate out of the braden head. Closed braden head and pressured casing to 400 psi. Shut in.

GPS: 38.80119 -098.77620

Perfs:

Top	Bot	Thru	Comments
2902	2916		
2891	2894		

Remarks: QUALITY CEMENTING TICKET # 6321

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel
CC:UIC ✓

(TECHNICIAN)

CM

KCC WICHITA

JAN 30 2015

JAN 30 2015

FEB 13 2015

RECEIVED

Form CP-2/3