

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-21842-00-01
Spot: NENWNW Sec/Twnshp/Rge: 27-22S-13W
324 feet from N Section Line, 1017 feet from W Section Line
Lease Name: MCMILLAN TRUST OWWO Well #: 1-27
County: STAFFORD Total Vertical Depth: 3951 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3943	2410	WITH 150 SX CMT
SURF	8.625	410		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/04/2015 10:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING Phone: (800) 433-9047

Proposed Plugging Method: SAND 50' ABOVE PERFS & 5 SX CMT. PLUG AT 770' WITH 12 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/04/2015 11:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 3600' WITH 5 SX CMT. 1ST PLUG AT 770' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 50 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3739	3742		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.


Plugged through: CSG

FEB 17 2015

CONSERVATION DIVISION
WICHITA, KS

2/18/15 OKM

District: 01

Signed 
(TECHNICIAN)

RECEIVED
FEB 10 2015
KCC DODGE CITY 