

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-02352-00-00
Spot: SENWSW Sec/Twnshp/Rge: 19-11S-20W
1650 feet from N Section Line, 4290 feet from W Section Line
Lease Name: MARTIN Well #: 2
County: ELLIS Total Vertical Depth: 3836 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3816		150 SX
SURF	8.58	229		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/04/2015 9:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: KENNETH C GATES Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 1000 # hulls, 4 bags C.C.
Milled on well since Jan 22 2015.
Milled to 1245'. Casing parted. Got stuck in casing. Got loosed and milled from 41' down. District supervisor approved plugging.
Perforations: 3620' - 3650'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2015 12:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Pratt Well Service ran in hole with tubing to 1235'. Global rigged to tubing, mixed and pumped 150 sx neat cement followed by 75 sx cement w/100 # hulls mixed in to circulate cement up 5 1/2" casing. Pulled tubing. Rigged to 5 1/2" casing and pumped 40 sx cement to pressure with 400 psi. Shut in pressure 150 psi. Rigged to 8 5/8" casing and pumped 25 sx cement to pressure with 300 psi. Shut in pressure 300 psi.

GPS: 39.07801 -099.58943
1691' FSL 4168' FEL
NW SE NW SW

Perfs:

Top	Bot	Thru	Comments
3620	3650		

Remarks: GLOBAL CEMENTING CO TICKET # 1580

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

KCC WICHITA

FEB 13 2015

RECEIVED

Form CP-2/3

FEB 06 2015