

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22628-00-01
Spot: SWNESW Sec/Twnshp/Rge: 11-6S-23W
1690 feet from S Section Line, 3610 feet from E Section Line
Lease Name: SCHUCK 15AD-11C Well #: 2
County: GRAHAM Total Vertical Depth: 3824 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3822		150 SX
SURF	8.625	256		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/28/2015 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 2013' w/250 sx cement.
Perforations: 3638' - 3642', 3655' - 3657', 3729' - 3735' and 3758' - 3762'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/28/2015 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3730' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 3100' and pumped 100 sx cement. Pulled tubing to 1705' and pumped 108 sx cement. Pulled tubing out and topped off with 25 sx cement full. Tied on to backside and squeezed w/0 sx cement full.
GPS: 39.54353 -099.85741

Perfs:

Top	Bot	Thru	Comments
3729	3735		
3655	3657		
3638	3642		

Remarks: CONSOLIDATED CEMENT TICKET # 47909

Plugged through: TBG

District: 04

Signed Mac [Signature] ^{2/18/15 CKM}
(TECHNICIAN) CM

KCC WICHITA
FEB 13 2015
RECEIVED