

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-175-22205-00-00  
Spot: NENENE Sec/Twnshp/Rge: 13-31S-31W  
360 feet from N Section Line, 268 feet from E Section Line  
Lease Name: MARY Well #: 1-13  
County: SEWARD Total Vertical Depth: 6003 feet

Operator License No.: 34322  
Op Name: STRAT LAND EXPLORATION CO  
Address: 15 E. 5TH ST., STE 2020  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5260		WITH 2 SX CMT
CIBP		5460		WITH 2 SX CMT
PROD	5.5	6003	1723	WITH 325 SX CMT
SURF	8.625	1519		WITH 775 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/27/2015 9:00 AM  
Plug Co. License No.: 35060 Plug Co. Name: HOLMAN WELL SERVICE, LLC  
Proposal Rcvd. from: STAN KARBER Company: HOLMAN WELL SERVICE, LLC Phone: (806) 435-0411

Proposed Plugging Method: SET CIBP @ 5460' & 2 SX CMT. SET CIBP @ 5260' WITH 2 SX CMT. PLUG AT 1680' WITH 10 SX GEL & 80 SX CMT. PLUG AT 540' WITH 540' WITH 40 SX CMT. PLUG AT 62' WITH 42 SX CMT.

Plugging Proposal Received By: ROBERT DICKERSON WitnessType: PARTIAL  
Date/Time Plugging Completed: 02/02/2015 3:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1/27/15: SET CIBP @ 5460' & 5260' WITH 2 SX CMT ON EACH. 2/2/15: 1ST PLUG AT 1795' WITH 20 BBL & 140 SX CMT. 2ND PLUG AT 567' WITH 10 BBL MUD & 60 SX CMT. 3RD PLUG AT 62' WITH 42 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5510	5518		
5310	5322		

RECEIVED  
KANSAS CORPORATION COMMISSION  
**FEB 17 2015**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS C CEMENT BY HOLMAN WELL SERVICE.

Plugged through: TBG

2/18/15 ocm

District: 01

Signed   
(TECHNICIAN)

RECEIVED  
FEB 10 2015  
KCC DODGE CITY