

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-21700-00-00
Spot: N2SEW Sec/Twnshp/Rge: 9-10S-21W
1650 feet from N Section Line, 1980 feet from W Section Line
Lease Name: LEWIS A Well #: 2
County: GRAHAM Total Vertical Depth: 3889 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3877		275 SX
SURF	8.625	264		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2015 12:00 AM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-2637

Proposed Plugging Method: Ordered 260 sx 60/40 pozmix 4% gel cement, 500 # hulls and 8 sx gel.
DV Tool at 1818' w/550 sx cement.
Perforations: 3698' - 3741'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2015 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:	Perfs:			
	Top	Bot	Thru	Comments
Ran tubing to 3596' and pumped 8 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1860' and pumped 125 sx cement w/200 # hulls. Good circulation of cement. Pulled tubing out and topped off casing w/25 sx cement. Tied on to backside and squeezed w/0 sx full at 300 psi. GPS: 39.20082 -099.67281	3698	3741		

Remarks: QUALITY CEMENT TICKET # 1081
Plugged through: TBG

District: 04 Signed: [Signature] (TECHNICIAN) CM
Date: 2/18/15 CKM

KCC WICHITA

FEB 13 2015
RECEIVED