

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-21783-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 2-12S-17W
2310 feet from N Section Line, 330 feet from W Section Line
Lease Name: HALL D Well #: 5
County: ELLIS Total Vertical Depth: 3690 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3689		300 SX
SURF	8.625	270		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/06/2015 9:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 885-8240

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3316' - 3320' Toronto, 3368' - 3546' LKC.
Operator Elected all cement plug. DV Tool at 1172' w/250 sx cement.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2015 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Pratt Hawk ran in hole with tubing to 3310'. Allied rigged to tubing, mixed and pumped 100 sx cement w/300 # hulls mixed in. Pulled tubing to 1850' and pumped 135 sx cement w/200 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing w/45 sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 5 sx cement to pressure with 200 psi. Shut in pressure 200 psi.

GPS: 39.03921 -099.18480
2966' FSL 4933' FEL
SW SW SW NW

Perfs:


Top	Bot	Thru	Comments
3368	3546		
3316	3320		

Remarks: ALLIED CEMENTING TICKET # 055653

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

2/18/15 CKM

CM

KCC WICHITA

FEB 13 2015

RECEIVED

FEB 06 2015