

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22500-00-01
Spot: NWSE Sec/Twnshp/Rge: 32-33S-13W
1900 feet from S Section Line, 1980 feet from E Section Line
Lease Name: SPRIGGS B Well #: 3
County: BARBER Total Vertical Depth: 4965 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	56		WITH 60 SX CMT
PROD	5.5	4957	794	WITH 290 SX CMT
SURF	8.625	221		WITH 140 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/28/2015 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 01/28/2015 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP DOWN 5 1/2" CASING 250# HULLS & 25 SX CMT. PRESSURE TO 500 PSI. 1ST PLUG AT 794' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4139	4143		

Received
KANSAS CORPORATION COMMISSION
FEB 12 2015
CONSERVATION DIVISION
WICHITA, KS

Received
KANSAS CORPORATION COMMISSION
FEB 12 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Ken Jehlik by 59
(TECHNICIAN)

RECEIVED
FEB - 2 2015
KCC DODGE CITY