

2 0505.11

3-31-86 191-30013-0000

API NUMBER 15-191-30013-06-00

SW, SEC. 16, T 30 S, R 1 W/EX

feet from S section line

feet from E section line

Lease Name Bell "B" Well # 2

County Sumner 117.65

Well Total Depth 3620 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 381

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Operator: Donald C. Slawson

Name & Address 200 Douglas Building

Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso License Number

Address

Company to plug at: Hour: 8:00 am Day: 5 Month: 3 Year: 19 87

Plugging proposal received from

(company name) (phone)

were: 4 1/2" casing was set at 3619' with 100 sacks cement. Top of cement was 3219'.

Perforated at 3542-48. Sand back to 3490' and dump four sacks cement.

Shut and pull pipe. Squeeze 8 5/8 with 3 hulls, 15 gel and 150 sacks cement.

STATE CORPORATION COMMISSION

APR 7 1987

Plugging Proposal Received by Warren Kirkpatrick (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00 A Day: 31 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT Sanded back to 3490' and dumped four sacks cement. Shot and

pulled 3000' of 4 1/2" casing on 3-5-87. Squeezed 8 5/8 with six sacks hulls,

15 sacks gel and 150 sacks cement. Hole in surface could not squeeze. On

On April 1, 1987, ran tubing to 450' and circulated cement to surface. Pulled

tubing. Put on swedge and squeezed 30 sacks cement out of hole to surface.

Remarks: Allied #1237

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not XXXXX) observe this plugging.

DATE 4-8-87

Signed: [Signature] (TECHNICIAN)

INV. NO. 16525

3-31