

To: 1 040817 1-4
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,353-0000
NW SE SE, SEC. 18, 7 34 S, R 13 W/E
990 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5171
Operator: Marathon
Name & Address RR 1, Box 125
Medicine Lodge, KS 67104

Lease Name Graves Well # G-1
County Barber
Well Total Depth 5050 164.13 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 380

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 10 a.m. Day: 4 Month: 1 Year: 1994
Plugging proposal received from Jeff Sletto
(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" at 4983' w/150 sx cement, PRTD 4893'. Perfs at 4712-22'
1st plug sand back to 4660' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:30 a.m. Day: 4 Month: 1 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 4660' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, 100 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3750' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED ~~1-28-94~~ observe this plugging.

DATE 1-28-94
INV. NO. 39823

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1994

CONSERVATION DIVISION
Wichita, Kansas