

To: 1040713
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-21 API NUMBER 15- 007-21,099-0000 18/4
W/2 SE SW, SEC. 18, T 34 S, R 13 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635
Operator: Great Bend Casing Pullers, Inc.
Name:
Address: P.O. Box 251
Great Bend, KS 67530

660 feet from S section line
3630 feet from E section line
Lease Name Bouziden Well # 18-1
County Barber
Well Total Depth 4990 162.18 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 246

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 12:10 p.m. Day: 21 Month: 10 Year: 19 92

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4984' w/300 sx cement, PBD 4940', Perfs at 4640-44, 4835-42, 4905-10'
1st plug sand back to 4590' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
10 3/4" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 21 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4550' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10
sx gel, 100 lbs. hulls and 150 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3217' of 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE 11-4-92
INV. NO. 36680

Signed Stephen J. Phipps
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1992