

2 100060

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 191-21,857-0000  
CNWSESW, SEC. 20, T 34 S, R 3 (W)RX  
990 feet from N/S section line  
3630 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4009

Lease Name Subera Well # 1-20

Operator: Forney Oil Corporation  
Name & Address 1601 N.W. Expressway  
Oklahoma City, OK 73118

County Sumner 161.56  
Well Total Depth 4971 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size \_\_\_\_\_ feet

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis, Inc. License Number 5420  
Address ElDorado, KS 67042

Company to plug at: Hour: \_\_\_\_\_ Day: 16 Month: 9 Year: 19 85

Plugging proposal received from Floss  
(company name) White & Ellis (phone) \_\_\_\_\_

were: 35 sacks at 1250 feet - 35 sacks at 275 feet - 25 sacks on wood and rubber  
bridge at 60 feet - 10 sacks in the rat hole

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XX

Operations Completed: Hour: 4:45P Day: 16 Month: 9 Year: 19 85

ACTUAL PLUGGING REPORT Ran drill pipe to 1250 feet and spot 35 sacks of cement. Pulled  
pipe to 275 feet and spot 35 sacks of cement. Pulled pipe to 60 feet and  
spotted 25 sacks of cement over wood and rubber bridge. Ran one joint of  
drill pipe in rat hole and circulated 10 sacks of cement to surface.

RECEIVED  
STATE CORPORATION COMMISSION

9-18-85  
SEP 18 1985

Remarks: 50/50, 6% gel, 3%cc  
(If additional description necessary, use BACK of this form.)

Halibarton ticket # 088025

INVOICED

DATE 9-18-85

INV. NO. 10149

9-16

JK

Signed J.L. Sanders  
(TECHNICIAN)