

2-100662

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-191-22,178-0000

NE NE SW, SECTION 20 TOWNSHIP 34 RANGE 3W

OPERATOR LICENSE # 6785

2430 FEET FROM S SECTION LINE  
3800 FEET FROM E SECTION LINE

OPERATOR Schulein Company  
NAME & 1776 Lincoln St. #811  
ADDRESS Denver, CO 80203

LEASE NAME: Subera #11-20

COUNTY: Sumner

WELL TOTAL DEPTH: 4805' *156.16*

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 274'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Red Tiger Drilling Co.  
ADDRESS: 1720 KSB Bldg., Wichita, KS 67202 LICENSE: 5302

COMPANY TO PLUG AT: HOUR: 11:00a DAY: 21 MONTH: 11 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Mike  
COMPANY NAME: Red Tiger Drilling Co. PHONE: \_\_\_\_\_

WERE: 35 sx @ 1000' - 35 sx @ 600' - 35 sx @ 325' - 25 sx @ 60' - 15 sx R.H.

PLUGGING PROPOSAL RECEIVED BY: Glenn Ward

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (     ) PART (     ) NONE ( X )

COMPLETED: HOUR: 11:30a DAY: 21 MONTH: 11 YEAR: 1990

ACTUAL PLUGGING REPORT:  
Drill mud @ 4800' to 1000' - spotted 35 sx cmt from  
1000' to 870' - mud to 600' - spotted 35 sx cmt from  
600' to 470' - mud to 325' - spotted 35 sx cmt from  
325' to 220' - mud to 60' - circ cmt to surf w/25 sx -  
put 15 sx in rat hole.

REMARKS: Howco #054525 60/40 4% gel

I DID NOT OBSERVE THIS PLUGGING.

**INVOICED**

DATE 1-4-91

INV. NO. 30322

*John Sanders*  
John Sanders (AGENT)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 19 1990

CONSERVATION DIVISION  
Wichita, Kansas  
FORM CP-273  
REV. 3/90