

15-025-10146-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Ashland Oil & Refining Company
Complete Address: Box 18695, Oklahoma City, Oklahoma 73118
Lease Name M.C. Harper Well No. 2
Location SW NE Sec. 4 Twp. 34 Rge. 21 ~~XXX~~ (W)
County Clark Total Depth 5522'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: None

Plugging Contractor: Toland & Johnston

Address: Box 94336, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 4:00PM Day 24 Month 10 Year 1968

The Above well was plugged as follows:

13 3/8" to 497' circulated w/ cement. 8 5/8" to 2385' cemented.
5 1/2" to 5518' cemented Top perforations 5429'
Plug bottom w/ 30 sacks cement. Top of cement 5000'
Mud 5000' to 500' Spotted 50 sacks cement 5000' to 400'
Mud 400' to 40' Plug, Hulls & 20 sacks cement 40' to 0'.
Getco Pump co. Pulled 1201' of 8 5/8" casing.
Pulled 3502' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eves
Well Plugging Supervisor

DATE 10/28/68

INV. NO. 8710-u