

15-025-10147-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Oklahoma

Lease Name M.C. Harper Well No. 3

Location NE SE Sec. 4 Twp. 34 Rge. 21 ~~EA~~ (W)

County Clark Total Depth 5501'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Gayle E. Toland

Address: Box 94336, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 2:00 PM Day 25 Month 6 Year 1968

The Above well was plugged as follows:

13 3/8" to 495' circulated w/ cement. 8 5/8" to 2392' cemented

5 1/2" to 5487' cemented. Top perforations 5412'

Plug bottom w/ 30 sacks cement Top of cement 5000'

Mud 5000' to 495' Spotted 50 sacks cement 495' to 395'

Mud 395' to 45' Plug, Hulls & 20 sacks cement 45' to 0'

Company Pump. Pulled 978' of 8 5/8" casing

Pulled 3516' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eves  
Well Plugging Supervisor

DATE 6-27-68

INV. NO. 8010-W