

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-025-20063-00-01 (of this well)

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W. Douglas, Suite 300-Wichita, Ks. 67202

Lease Name Harper Ranch Well No. 1

Location SE SE NW Sec. 12 Twp. 34s Rge. 21 (E)    (W) X

County Clark Total Depth 5500

Abandoned Oil Well    Gas Well X Input Well    SWD Well    D & A   

Other well as hereafter indicated   

Plugging Contractor Sargent's Casing Pulling.

Address 630 S. Lincoln, Liberal. Ks. 67901 License No. 511

Operation Completed: Hour 3 Pm. Day 26 Month 9 Year 1979

The above well was plugged as follows:

100' 12 3/4" casing w/450 sax cement-615' 8 5/8" casing. 4 1/2" casing  
set at 5416'-Open hole-Sargent mixed & pumped 25 sax cement in 4 1/2"  
casing to 5000'-Pull 3031' 4 1/2" casing-Pump 40 sax cement through  
4 1/2" casing to 600'-Bridge at 35' & 10 sax cement to top of casing.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 28 1979

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 9/28/79

INV. NO. 0591-w

15-025-20063-00-01

DRILLERS' LOG

RECEIVED  
FEB 11 1975  
RECEIVED

TEXAS OIL & GAS CORP.  
No. 1 Harper Ranch  
SE SE NW, Sec. 12-34S-21W  
Clark County, Kansas

*Well File  
Copy to Dallas*

Elevation: 1884 K.B.

Commenced: 12-30-74  
Completed: 1-16-75

Surface Casing: 607' of  
8-5/8" cemented w/250 sx  
Halco-Lite, 125 sx common  
cement, 3%cc. Re-Cemented  
thru 2" Tubing w/100 sx  
common cement, 3% cc.  
1-2-75

FORMATION

DEPTH

Surface Hole	0 - 615
Red Bed & Shale	615 - 1275
Anhy Strks & Anhy	1275 - 1390
Red Bed & Lime Strks	1390 - 1515
Shale	1515 - 1845
Shale & Lime	1845 - 2235
Lime & Shale	2235 - 3935
Lime	3935 - 4097
Lime & Shale	4097 - 4573
Lime	4573 - 5125
Lime & Shale	5125 - 5168
Lime	5168 - 5293
Lime & Shale	5293 - 5400
Lime	5400 - 5432 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 27th day of January, 1975.

My Commission Expires: RECEIVED  
August 25, 1976 STATE CORPORATION COMMISSION

*Ella Priess*

Ella Priess, Notary Public

SEP 19 1979

CONSERVATION DIVISION  
Wichita, Kansas

*Ella Priess*  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Com. Expires Aug. 25, 1976