

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-025-20,430-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Hummmon Corporation

Complete Address 400 One Main Place, Wichita, Kansas 67202

Lease Name Katherine Well No. 1

Location 200' NSE-SE NW Sec. 12 Twp. 34 Rge. 21 (East)(West)

County Clark Total Depth 5510'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation

Address 107 W. Fowler Medicine Lodge, Kansas 67104 License No. 583

Operation Completed: Hour: 3:30 PM Day: 30 Month: April Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran 5508' of 4 1/2" production pipe with the plug back at 5468'. Then they perforated from 5412' to 5414'. 1st plug sandbed off bottom to 5390' + put 4 bbl of cement in top of sand. 2nd plug pumping through swedge on surface casing. They 6 bbl of hulls 10 bbl of Jell + 150 bbl of cement. The cement used was common with 3% C.C. They recovered 4400' of 4 1/2" production pipe.

Allied Cementing accomplished the plugging. Shut in at 480 lbs. Amount of Surface Casing: 626' of 8 1/2" cement circulated with 200 bbl of cement

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

MAY - 6 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 5-7-82

INV. NO. 127-4