

15-025-10125-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Clark
Location: CSE NE Sec. 30 Twp. 34S Rge. 31 (E) (W) W
Name of Field: _____ Total Depth: 5546

I have this date completed supervision of plugging of:

Lease Name: Harper Well No. 1
Operator's Full Name: Sunray Mid-Continent Oil Co.
Complete Address: 503 Central Bldg, Wichita, Kans.
Plugging Contractor: Toland + Reeves
Address: Woodward Plaza License No. _____
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 17 Month February Year 1960

The above well was plugged as follows:

1773' of 8" surface casing annulated with cement -
4 1/2" set at 5339'. Pumped cement from bottom to
5300'. Pulled 5008' of 4 1/2". Filled hole to 550' of
with heavy mud. Rock bridge set from 550 to
530'. Back cement dumped on bridge. Hole
filled to 40' with heavy mud. Rock bridge from
40' to 30'. Cement poured to base of cellar.

Signed: W. H. Kemp
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 3/2/60
INV. NO. 974-u