

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSION

AUG 8 1963

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Morgenstern & Spector Inc.

Complete Address: P. O. Box 661, Russell, Kansas

Lease Name Fitzsimmons "B" Well No. # 2 "A"

Location NW NE NW Sec. 2 Twp. 28 Rge. 11 (E) (W) W

County Pratt Total Depth 3535½

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Co.

Address: Route 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 1:00PM Day 6th Month August Year 1963

The Above well was plugged as follows:

400' of 8 5/8" surface pipe, cement circulated. 3514' of 5½" long string,  
cemented with 300 sacks. Hole was sanded to 3500', cemented with 5 sacks.  
Hole was flowing water and a squeeze job is necessary. 10 sacks of mud  
and 80 sacks cement was pumped in hole through a swage in the surface  
pipe, at a pressure of 800 lbs. This cementing was done by Lynch Casing  
Pulling Co.

2025' of 5½" long string was recovered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging SupervisorDATE 8/8/63  
INV. NO. 7535-W