

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15- -

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Costal Oil & Gas Corp # 6953

Complete Address Box 1332, Amarillo Texas 69189

Lease Name Mr. Clain Well No. 1-33

Location C-NE-NE-8W Sec. 33 Twp. 33 Rge. 42 (East) (West)

County Morton Total Depth 3285'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Sargent's casing Pulling

Address 620 S. Lincoln Box 506 Liberal, Kansas 67901 License No. 837

Operation Completed: Hour: 3:00 PM Day: 4 Month: 10 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

5 1/2" @ 3273' perf @ 2657' to 3186' 1st plug 5 1/2" sandbed back to
2605' on top of packer & dumped 2 bbl cement on top of sand
and plug @ 1050' w/ 35 bbl cement. 3rd plug @ 650' w/ 35 bbl
cement. 4th plug on solid bridge @ 40' to 0' w/ 10 bbl cement.
The 2, 3 & 4th plugs were pumped through tubing. They
recovered 2130' of 5 1/2" pipe. The plugging was
accomplished by Sargent's pipe pulling. Cement
used was common.

Amount of Surface Casing: 8 5/8" @ 625'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION
RECEIVED
OCT 12 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 10-25-82

INV. NO. 1461-W