

*Y*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Fannie "A" Well No. # 3

Location C NE NW NE Sec. 6 Twp. 28 Rge. 13 (E) (W) W

County Pratt Total Depth 4506'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950 El Dorado, Kansas License No. 547

Operation Completed: Hour 9:00 AM Day 26th Month June Year 1965

The Above well was plugged as follows:

469' of 9 5/8" surface pipe, cement circulated. 4500' of 7" long string,  
cemented with 115 sacks. Plug back to 4149'. Top perferation 4059', Plug  
was pushed to 4040', and 50' of rock bridge, and cemented with 5 sacks.  
3500' of 7" long string was recovered from the hole. Fluid was up in the  
hole. Bridge plug was pushed in fluid to 270', and 10' of rock bridge on  
plug. 5 sacks of cement was mixed in barrel and put on plug at 260', through  
the dump bailer, and let set over-night. Next morning hole was bailed dry,  
and 23 sacks of cement was added to the plug. Hole was filled with mud to 40',  
and 10' of rock bridge, and cemented with 12 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
**RECEIVED**  
STATE CORPORATION COMMISSION

Signed: Archie Elving  
Well Plugging Supervisor

DATE 6/28/65 JUN 28 1965

INV. NO. 136244  
CONSERVATION DIVISION  
Wichita, Kansas