

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1973
CONSERVATION DIVISION
Wichita, Kansas
15-077-20120-0000

Operator's Full Name Kathol Petroleum Inc

Complete Address 900 Sutton Place Wichita, KS

Lease Name Mathes Well No. 2

Location C SW/NE Sec. 10 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4393

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Ralph Comstock Pipe Pulling Co Inc

Address Stafford, KS License No. 490

Operation Completed: Hour 11:00 AM Day 10 Month 2 Year 1973

The above well was plugged as follows:

252 ft 10 3/4 surface cemented with 250 sacks. 4382 ft 7" long
string cemented with 150 sacks. Open hole. Sand to 4375 ft, 6 sacks
cement with bailer. Pulled 2410 ft 7". Set 10 ft rock bridge at
250 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed Russell Biberstein
Well Plugging Supervisor

DATE 2/12/73
INV. NO. 6959-W