

K
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-077-20068-0000

Operator's Full Name Kathol Petroleum Inc.

Complete Address 900 Sutton Place Wichita, Ks 67202

Lease Name Bolles Well No. 1

Location SW/SE Sec. 10 Twp. 31 Rge. 7 (E) (W)

County Harper Total Depth 4390

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated Prairie Oil Field Service

Plugging Contractor Forbes Casing Pulling Co. Inc.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 4:00 PM Day 18 Month 7 Year 1970

The above well was plugged as follows:

249 ft of 8 5/8 surface pipe cemented with 200 sacks. 4348 ft of 5 1/2
long string cemented with 100 sacks. Set plug at 4300 ft, 30 gal.
sand & 5 sacks cement with bailer. Pulled 3750 ft of 5 1/2. Set 10 ft
rock bridge at 240 ft. Fill with 4 yds redimix to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *L. Russell Bilveston*
Well Plugging Supervisor

DATE 7/20/70
INV. NO. 2264-W