

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

25 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-071-009 68-0005

Operator's Full Name Pickrell Drlg. Co.

Complete Address 705 4th Natl Bldg. Wichita, Ks

Lease Name Darnes A Well No. 3

Location NW/SW/SW Sec. 24 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4462

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1182 Great Bend, Ks License No. 623

Operation Completed: Hour 2:00 PM Day 23 Month 8 Year 1972

The above well was plugged as follows:

295 ft 8 5/8 surface pipe cement circulated. 4458 ft 5 1/2 long string

cemented with 150 sacks. Top perf. 4374 ft. Sand to 4350 ft,

5 sacks cement with bailer. Pulled 3615 ft 5 1/2. Set 10 ft rock bridge

at 280 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8/25/72

INV. NO. 6226-W