

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-077-19050-0000

RECEIVED
STATE CORPORATION COMMISSION
NOV 2 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drlg Co
Complete Address 705 4th Natl Bldg Wichita, KS
Lease Name Darnes B Well No. 2
Location NE/NW/NE Sec. 24 Twp. 31s Rge. 9 (E) W
County Harper Total Depth 4446
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling Co Inc
Address Box 1182 Great Bend, KS License No. 623
Operation Completed: Hour 4:00 PM Day 31 Month 10 Year 1973

The above well was plugged as follows:

305 ft 8 5/8 surface cemented with 250 sacks. 4446 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 4350 ft. Sand to 4300 ft, 5 sacks
cement with bailer. Pulled 3325 ft 5 1/2. Set 10 ft rock bridge at
260 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/2/73
INV. NO. 8102-W

Signed: Russell Bihorst
Well Plugging Supervisor