

40  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 30 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued January 23, 1967

15-077-10104-0000

Operator's Full Name El Dorado Supply Company

Complete Address: Box 422, El Dorado, Kansas

Lease Name Darnes Estate Well No. 1-"B"

Location NW NE SW Sec. 24 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4418'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 12:30PM Day 27th Month Jan. Year 1967

The Above well was plugged as follows:

230' of 8 5/8" surface pipe, cement circulated. 4418' of 5 1/2" long  
string, cemented with 75 sacks. Top perferation 4407'. Bottom of the  
hole was sanded to 4400', and cemented with 5 sacks, through the dump  
bailer. 3800' of 5 1/2" long string was recovered from the hole. Hole  
was filled with mud to 220', bridge plug and rock bridge from 220' to  
210', and cemented with 25 sacks. Hole was filled with mud to 40',  
rock bridge from 40' to 30', and cemented with 10 sacks to the base  
of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 1/30/67  
INV. NO. 4679-W