

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20272-00-00  
Spot: W2NENWNW Sec/Twnshp/Rge: 7-33S-31W  
330 feet from N Section Line, 830 feet from W Section Line  
Lease/Unit Name: GRABER Well Number: 3  
County: SEWARD Total Vertical Depth: 4424 feet

Operator License No.: 6568  
Op Name: KAISER-FRANCIS OIL COMPANY  
Address: PO BOX 21468  
TULSA, OK 74121

Conductor Pipe: Size feet: 3 1/4 3.78  
Surface Casing: Size 8.625 feet: 1539 WITH 250 SX CMT  
Production: Size 5.5 feet: 4374 WITH 150 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/05/2002 10:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: LOAD HOLE WITH MUD. SET CIBP @ 4200' WITH 2 SX CMT. 1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/05/2002 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 4375'. PERFS AT 4247-83'. CIBP @ 4200' WITH 2 SX CMT. LOADED HOLE & PRESSURED 5 1/2" TO 700'. HELD. 1ST PLUG PULLED OUT OF HOLE TO 1570'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH CASING TO 600'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT.

RECEIVED  
MAR 11 2002  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed

Jim Holland PRT II  
(TECHNICIAN)

INVOICED

MAR 07 2002

DATE

Mar 12, 02

WV. NO.

2002061509

Form CP-2/3

MP