

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

15-677-30068-0001

old well

C-SE/NE, Sec. 10, T 31 S, R 7 W/8

feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

feet from W/E section line

Operator License # 7380

Lease Name Mathes Well # SWD

Operator: Indian Wells Oil Co.
Name & Address Box 322 Haysville Ks.

County Harper

Well Total Depth 4798 feet

\$155.94

Conductor Pipe: Size feet

Surface Casing: Size 8 7/8 feet 2 8/16

Abandoned Oil Well Gas Well Input Well SWD Well ☒ D&A

Other well as hereinafter indicated

Plugging Contractor Gressel Corp. License Number 5822

Address Box 322 Haysville, Ks. 67060

Company to plug at: Hour: 1:00 PM Day: 15 Month: April Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Dewey Gressel

(company name) Gressel Corp

(phone) 788-2888

were: Bottom. 5 1/2" Pipe set @ 4798 w/ 300 SX.

Simpson Perf. from 4740-4741 ft. Mississippi Perf.

4246 to 4370. Model A.D. Packer shot of @ 4415

with 28' of 2" tubing. and E.Z. Drill Howco Packer

set @ 4298' & cemented with 50 SX. Type A. spotted

another 50 SX @ 3298

Signed

Glenf. Ward
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part None

Operations Completed: Hour: 10:00 AM Day: 20 Month: April Year: 1983

ACTUAL PLUGGING REPORT top Plug. Pumped 150 SX

Type A cement with 5% oil & 3% ca. thru

8 5/8 swage, max. PSI. 250' closed in

@ 250 PSI.

Howco ticket - 154592

Remarks:

I hereby certify that the above plugging instructions were given as herein stated
and that I (did) did not) observe this plugging.

INVOICED

DATE 5-4-83

INV. NO. 4156-W

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1983

CONSERVATION DIVISION
Wichita, Kansas

Signed

Glenf. Ward
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82