

2-27

2-0040872

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

15-077-10099-0000

API NUMBER: DRILLED 10/30/54

NW NW NW, SECTION 24 TOWNSHIP 31 T³KCC RANGE 22 9W

OPERATOR LICENSE # 31532 4620 FEET FROM S SECTION LINE
OPERATOR BISON PRODUCTION COMPANY 660 FEET FROM E SECTION LINE
NAME & 9320 EAST CENTRAL
ADDRESS WICHITA, KS 67206

LEASE NAME: DARNES RANCH #1
COUNTY: HARPER
WELL TOTAL DEPTH: 4500' 146,25'
PIPE: _____
SURFACE CASING: 8 5/8" @ 197'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE

ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: RUSSEL MEYERS

COMPANY NAME: BISON PRODUCTION COMPANY PHONE: _____

WERE: 5 1/2" AT 4499' 35 SACKS AT 1425'
PERFS 4406'-4418' 35 SACKS AT 950'
CIRCULATE 250'- 0'
SAND TO 4350' AND 5 SACKS

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { _____ } PART { X } NONE { _____ }


COMPLETED: HOUR: 1:20 DAY: 27 MONTH: 2 YEAR: 1997

ACTUAL PLUGGING REPORT: THE PERFS WERE COVERED WITH SAND FROM 4500'-4350' AND CAPPED WITH 5 SACKS OF CEMENT. 5 1/2" RECOVERED FROM 1700' AND PULLED TO 1432' WHERE 35 SACKS OF CEMENT WAS SPOTTED. CASING PULLED TO 260' WHERE CEMENT WAS CIRCULATED TO SURFACE. REMAINING PIPE PULLED AND CEMENT TOPPED OFF.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT

INVOICED
DATE 3-10-97
INV. NO. 47709
2-27

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 10 1997
3-10-97
CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

STEVE VAN GIESON