

2 030848

9-13

47 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 191-22,128-00-00
NE NE NW, SEC. 23, T 34 S, R 02 W/EX

TECHNICIAN'S PLUGGING REPORT

4950 feet from S section line
2970 feet from E section line

Operator License # 3667

Lease Name Crane "A" Well # 1

Operator: Source Petroleum

County Sumner 152.75

Name & Address 200 W. Douglas, #820

Well Total Depth 4700' feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8-5/8 feet 257' CTS

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Co. License Number 5418

Address _____

Company to plug at: Hour: _____ Day: 13 Month: 9 Year: 19 89

Plugging proposal received from Vince Schrepel

(company name) Allen Drilling Company (phone) _____

were: 35 sx 4650' - 35 sx 843' - 35 sx 518' - 35 sx 300' - 25 sx 60' -

10 sx rat hole

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by _____ Dist #2
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 19:15 Day: 13 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT Filled hole/mud - ran dp to 4650' & spotted 35 sx - pulled
dp to 843' & spotted 35 sx - pulled dp 518' & spotted 35 sx - pulled dp to 300' &
spotted 35 sx - pulled dp 60' & spotted 25 sx to surface - pumped 10 sx cement in
rathole

Halliburton Services 60/40 posmix 6% gel

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

(If company did not observe this plugging.

DATE 9-22-89

Signed Don Thompson
(TECHNICIAN)

INV. NO. 25941
9-13