

1100255

TO: STATE CORPORATION COMMISSION

10-22

API NUMBER 15-129-20,640-00-00
C SE SW SEC. 2, T 33 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WORTHINGTON A WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY MORTON 165.75

OPERATOR LICENSE # 5447

WELL TOTAL DEPTH 5100' FEET

OPERATOR: OXY USA INC PRODUCTION CSG: SIZE 5 1/2" @ 5099' WITH 350 SX

NAME AND BOX 2528 SURFACE CASING: SIZE 8 5/8" @ 1359' WITH 650 SX

ADDRESS LIBERAL, KS 67950-2528 CONDUCTOR PIPE: SIZE 20" @ 43'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING INC LICENSE NUMBER 31151

ADDRESS RT 1 BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 21 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING (PHONE) 580-854-6515

WERE: PERFS AT 4569-4574

1ST PLUG MIX 300# HULLS WITH 25 SX CEMENT AND SPOT @ 4569' TO 4359'. 2ND PLUG AT 2400' TO

2300' WITH 30 SX CEMENT. 3RD PLUG AT 1380' WITH 50 SX CEMENT.

4TH PLUG AT 450' WITH 30 SX CEMENT.

5TH PLUG AT 40'-0' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 22 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG MIX 300# HULLS WITH 25 SX CEMENT AND SPOT AT 4569' TO 4359'. 2ND PLUG AT 2400' TO

2300' WITH 30 SX CEMENT. 3RD PLUG AT 1380' WITH 50 SX CEMENT.

4TH PLUG AT 450' WITH 30 SX CEMENT.

5TH PLUG AT 40' TO 0' WITH 10 SX CEMENT.

REMARKS: USED 135 SX NEAT CEMENT BY SARGENTS. RECOVERED 2419' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

11-6-98
60271

11-5-98
RECEIVED
STATE CORPORATION COMMISSION