

2-24

140 R

1 110125

API NUMBER 15-129-20,662-00-00

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 150'  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

S of NW SW SEC. 2, T 33 S, R 43 W  
1830 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Soupiset A Well # 3

Operator: OXY USA, Inc.

County Morton 164.13

Name & Address P.O. Box 26100

Well Total Depth 5050 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1367

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 23 Month: 2 Year: 19 89

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 5050' PBD 5023' Perfs at 4628-30, 4634-36' TOC 3728'

1st plug set CIBP at 4550' with 2 sx cement on top,

2nd plug at 1367' with 50 sx cement,

3rd plug at 550' with 30 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by James R. Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 24 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4550' with 20' of cement on top,

2nd plug pulled 15 joints to 2900' with 40 sx cement,

3rd plug pulled 40 joints to 1380' with 50 sx cement,

4th plug pumped 30 sx cement at 550',

5th plug pumped 10 sx cement at 40', mud between plugs.

RECEIVED  
STATE CORPORATION COMMISSION  
3-3-89  
MAR 03 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 3519' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If you observe this plugging.)

DATE 3-6-89

Signed James R. Kapp (TECHNICIAN)

INV. NO. 24059