

1060301

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,674-00-00
SW SE, SEC. 2, T 33 S, R 43 W EX
660 feet from N/S section line
1980 feet from W/SE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Soupiset Well # "C" 1

Operator: Cities Service Oil & Gas Corp.
Name & Address 3545 N.W. 58th Street
Oklahoma City, OK 73112

County Morton

Well Total Depth 5080 4 165.10 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1358

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Daco, Inc. License Number 6416

Address Drawer 3010, Borger, TX 79007

Company to plug at: Hour: 8:00 am Day: 16 Month: August Year: 19 84

Plugging proposal received from John White

(company name) Cities Service (phone) 316-624-1892

were: 5 1/2" set at 3868' PBTB 3807' Perfs 3559-64'

1st plug set CIBP at 3520' with 2 sx cement

2nd. plug pump 50 sx cement through stub at 2500'

3rd plug at 1400' with 50 sx cement 4th plug at 700' with 30 sx cement
solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:00 am Day: 16 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 3868' PBTB 3807' Perfs 3559-64'

1st plug set CIBP at 3520' with 2 sx cement, 2nd plug pumped 50 sx cement through
stub at 2201', 3rd plug at 1408' with 50 sx cement, 4th plug at 700' with 30 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10
sx cement.

STATE CORPORATION COMMISSION

AUG 24 1984

Remarks: Used common sacked cement by Daco. They recovered 225 CONSERVATION DIVISION 5 1/2" casing.
WICHITA, KANSAS

(If additional description is necessary, use BACK of this report.)

INVOICED (xxx) / did not observe this plugging.

DATE 8-28-84

Signed Paul A. Luthie (TECHNICIAN) 50

INV. NO. 3419

8-16