

1100329

TO: STATE CORPORATION COMMISSION

API NUMBER 15-129-20,763-0000  
C SE SE NE SEC. 3, T 33 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WORTHINGTON B WELL # 1-B

TECHNICIAN'S PLUGGING REPORT 2/1/00

COUNTY MORTON 164.65

OPERATOR LICENSE # 5447

WELL TOTAL DEPTH 5066 FEET

OPERATOR: OXY USA INC.

PRODUCTION CSG: SIZE 5 1/2" @ 5066' WITH 175 SX

NAME AND PO BOX 2528

SURFACE CASING: SIZE 8 5/8" @ 1372' WITH 725 SX

ADDRESS LIBERAL, KS 67905-2528

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 01 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 4117-23 & 4632-40

1ST PLUG SET CIBP AT 4600'. NO DOCUMENTATION OF ANY CEMENT ON TOP OF BRIDGE PLUG.

PRESSURE UP WITH MUD TP 300 PSI. HELD OKAY. 2ND PLUG SPOT 50 SX CEMENT AT 2802'.

3RD PLUG SPOT 50 SX CEMENT AT 1400'. 4TH PLUG SPOT 40 SX CEMENT AT 400'.

5TH PLUG SPOT 10 SX CEMENT FROM 40'-0'. PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:30 PM DAY: 01 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 4600'. NO DOCUMENTATION OF ANY CEMENT ON TOP OF BRIDGE PLUG.

PRESSURE UP WITH MUD TO 300 PSI. HELD OKAY. 2ND PLUG SPOT 50 SX CEMENT AT 2802'.

3RD PLUG SPOT 50 SX CEMENT AT 1400'. 4TH PLUG SPOT 40 SX CEMENT AT 400'. RECEIVED

5TH PLUG SPOT 10 SX CEMENT FROM 40' TO 0'. STATE CORPORATION COMMISSION

FEB - 3 2000

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 2802' of 5 1/2" CASING. CONSERVATION DIVISION  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM) Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING.

NOICED  
DATE 2/3/00  
NO. NO. 061210

SIGNED

Gary Winters  
(TECHNICIAN)

FORM CP-2/3