

To: 1 051533 2-21  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-129-21,114-0000 1462  
C NW SE, SEC. 4, T. 33 S, R. 43 WEX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: OXY USA INC.  
Name & Address P.O. Box 26100  
Oklahoma City, OK 73126-0100

1980 feet from S section line  
1980 feet from E section line

Lease Name Federal Well # 1-4

County Morton 167.37

Well Total Depth 5150 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1365

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gabbert & Jones License Number 5842

Address 333 E. English, Suite 215, Wichita, KS 67202

Company to plug at: Hour: 7:30 p.m. Day: 20 Month: 2 Year: 19 92

Plugging proposal received from Cal Wylie

(company name) OXY (phone) 316-697-4427

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1400' with 50 sx cement, 2nd plug at 700' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:30 a.m. Day: 21 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 4562-4462' with 30 sx cement,

2nd plug at 1450-1250' with 50 sx cement,

3rd plug at 700-468' with 50 sx cement,

4th plug at 55-5' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Class H Pozmix by Halliburton.  
(if additional description is necessary, use BACK of this form.)

I did not observe this plugging.

DATE 2-16-92

INV. NO. 34746

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1992  
CONSERVATION DIVISION  
WICHITA, KANSAS

FOR KGS USE: EFFECTIVE DATE: 1-28-92  
 DISTRICT # \_\_\_\_\_  
 3607 Yes  No

State of Kansas  
 NOTICE OF INTENTION TO DRILL 129-21,114

FORM MUST BE TYPED  
 FORM MUST BE SIGNED  
 ALL BLANKS MUST BE FILLED

Must be approved by the K.S.C. five (5) days prior to commencing well

Expected Spud Date February 1, 1992  
 month day year

Spot CNW/4 SE/4 Sec 4 Twp 33 S. Rg 43 East  West

OPERATOR: License # 5447  
 Name: OXY USA INC.  
 Address: P.O. Box 26100  
 City/State/Zip: Oklahoma City, OK 73126-0100  
 Contact Person: Raymond Hui  
 Phone: (405) 749-2471

1980' feet from South / ~~XXXX~~ line of Section  
 1980' feet from East / ~~XXXX~~ line of Section  
 IS SECTION  REGULAR  IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)  
 County: Morton  
 Lease Name: Federal Well #: 1-4  
 Field Name: N. Winter

CONTRACTOR: License #: Undertermined at this time.  
 Name: Will report on ACO-1) Gabbert & Jones

Is this a Prorated/Spaced Field? yes  no  
 Target Formation(s): Morrow

Well Drilled For: Well Class: Type Equipment:  
 Oil =  Enh Rec  Infield  Mud Rotary  
 Gas  Storage  Pool Ext.  Air Rotary  
 OWMO  Disposal  Wildcat  Cable  
 Seismic;  # of Holes  Other  
 Other  
 If OWMO: old well information as follows:  
 Operator: \_\_\_\_\_  
 Well Name: \_\_\_\_\_  
 Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Nearest lease or unit boundary: 1980'  
 Ground Surface Elevation: 3619' feet MSL  
 Water well within one-quarter mile: yes  no

Depth to bottom of fresh water: 300'  no  
 Depth to bottom of usable water: 300'

Surface Pipe by Alternator:  1  2  
 Length of Surface Pipe Planned to be set: 1400'

Length of Conductor pipe required: 30'  
 Projected Total Depth: 5150'

Formation at Total Depth: Chester  
 Water Source for Drilling Operations:  
 well  farm pond  other

Directional, Deviated or Horizontal wellbore? yes  no  
 If yes, true vertical depth: \_\_\_\_\_  
 Bottom Hole Location: \_\_\_\_\_

OWR Permit #: \_\_\_\_\_  
 Will Cores Be Taken? yes  no  
 If yes, proposed zone: \_\_\_\_\_

320' Alt. I Req.

**AFFIDAVIT**

Exp. 7/23/92

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
 It is agreed that the following minimum requirements will be met:

1. Notify the appropriate district office prior to spudding of well;

RECEIVED  
 STATE COMMISSION

FEB 2 1992  
 STATE COMMISSION

Pusher Caul w/ oxy

SPUD DATE 2-10-92 INIT. S.P.

LENGTH SURFACE PLANNED 1435' of 2 1/2"  
 RESERVE PIT STATUS- REMOVE FLUID LINED  
 after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE  
 SURFACE PIPE 8 1/2" @ 1365 CONDUCTOR  
 ANHYDRITE T- B- ELEVATION \_\_\_\_\_

TD 5150 FORMATION \_\_\_\_\_

RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE  
 \_\_\_\_\_ SX \_\_\_\_\_ Y \_\_\_\_\_ N

Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

Hug./Council @ 45 62- Ft. W/ 30 SX  
1450-1250

Anhydrite Base @ 1400 Ft. W/ 50 SX  
800-467

1/2 Base Anyh. @ 700 Ft. W/ 50 SX

1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

Bottom Surface @ 55-5 Ft. W/ \_\_\_\_\_ SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
 Hauling \_\_\_\_\_

TECHNICIAN A.L. DATE 2-20-92

TYPE OF CEMENT 60/40 Poz 6'000

STARTING TIME 7:30 (AM/PM) DATE 2-20-92

COMPLETION TIME 2:30 (AM/PM) DATE 2-21-92

CEMENT COMPANY Hall