

1 030387

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-129-20.749-00-00  
150' SW of C NW SW, SEC. 12, T 33 S, R 43 W/X

1874 feet from S section line

4726 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469

Lease Name Hatterman "A" Well # 2

Operator: Anadarko Production Company

County Morton 162.83

Name & Address P. O. Box 351

Well Total Depth 5010 feet

Liberal, KS 67901

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1315

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wakefield Oil Company, Inc. License Number 5662

Address P. O. Box 548, Winfield, KS 67156

Company to plug at: Hour: 8:00 pm Day: 27 Month: March Year: 19 85

Plugging proposal received from Chuck Nelson

(company name) Anadarko (phone) 316-624-6253

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4447' with 50 sx cement

2nd plug at 2600' with 50 sx cement

3rd plug at 1350' with 50 sx cement

4th plug at 780' with 25 sx cement

solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx. Steve Durrant

7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate mouse hole with 10 sx cement. Gave water well to Government

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:00 pm Day: 27 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 4447' with 50 sx cement, 2nd plug at 2600' with 50 sx cement, 3rd plug at 1350' with 50 sx cement, 4th plug at 780' with 25 sx cement, 5th &

6th plug solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rat hle with 10 sx cement, 8th plug to circulate mouse hole with 10 sx cement. Gave water well to Government

RECEIVED  
STATE CORPORATION COMMISSION

'APR 04 1985

Remarks: Used Common cement by Halliburton. CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form.)

INVOLVED

(If not) observe this plugging.

DATE 4-8-85

Signed Steve Durrant (TECHNICIAN)

INV. NO. 7005

3-27