

2 090034

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 191-20, 245-00-01

150' NWCNWSE, SEC. 6, T 34 S, R. 4 W/EX

2086 feet from ~~NW~~ section line

2086 feet from ~~NE~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8759

Lease Name Matahla Well # 3

Operator: Mack Energy Co.]

County Sumner

Name & Address Box 400

Well Total Depth 4750 154.38 feet

Duncan, OK 73534

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 246'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rains & Williams License Number 5146

Address 435 Page Court, 220 W. Douglas, Wichita, Ks. 67202

Company to plug at: Hour: 8:00p.m. Day: 3 Month: 8 Year: 19 84

Plugging proposal received from Warren Kirkpatrick

(company name) K.C.C. (phone)

were: 10 Gel 1 hull, 40 sacks 60-40 at 825'; 2% gal; ~~35 sacks at 675'~~; 35 sacks at 300'; 25 sacks at 60'; 10 in rat

K.C.C. Plugging Proposal Received by Warren Kirkpatrick (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:55p.m. Day: 3 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT approximately 450' of drill collars and 3475' of drill pipe pulled into at a 180,000 lb. pull; Acme of Great Bend fished for three days, finally gave up, pipe left in hole; hole filled with heavy drilling mud; run drill pipe to 825'; spotted 40 sacks cement through drill pipe; pulled drill pipe to 300' spotted 35 sacks of cement through drill pipe; pulled drill pipe to 60' spotted 25 sacks cement through drill pipe on top of a wood and rubber plug; one joint of drill pipe was run in rat hole, circulated 10 sacks of cement to surface

Remarks: HOWCO Ticket #892276

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 8-16-84

AUG 15 1984 Signed David Weitz (TECHNICIAN)

INV. NO. 3214

CONSERVATION DIVISION
Wichita, Kansas