

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,408 -0000

N/2 N/2 SW, Sec. 11, T 28 S, R 13 (W/E)

2310 feet from NXS section line NW/1/4

1320 feet from W/K section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Withers Well # 1

Operator: VAC Petroleum
Name & 6225 East Kellogg
Address Wichita, KS 67218

County Pratt

Well Total Depth 4555 feet 148.03

Conductor Pipe: Size feet

Surface Casing: Size 3 5/8 feet 264

316-685-0111

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Cougar Drilling Co., Inc. License Number 5138

Address 555 North Woodlawn # 114, Wichita, KS 67208

Company to plug at: Hour: 12:00 pm Day: 5 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Gary Bagby

(company name) Cougar (phone) 316-659-3173

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 720' with 50 sx cement

2nd plug at 300' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole
with 10 sx cement. Plug water well with
5 sx cement

Signed J. H. May (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:00 pm Day: 5 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 720' with 50 sx cement, 2nd plug at 300' with 40
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rathole with 15 sx cement, 6th plug to
circulate mousehole with 10 sx cement. Plug water well with 5 sx cement.

Remarks: Use 60/40 Pozmix with 2% gel 3% cc. by Halliburton Ticket No. 745816

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed J. H. May (TECHNICIAN) ✓

INVOICED

DATE 2-24-84

INV. NO. 0371

2-5