

1 010219

MAR 6 1987

API NUMBER 15- N/A

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NE/4, SEC. 16, T 28 S, R 13 W/E  
3960 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3055

Lease Name LCP Corp Well # 1

Operator: Petrie Exploration Company, Inc.  
Name & Address Rt. 1  
Pratt, KS 67124

County Pratt 109.58  
Well Total Depth 3310 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 10 3/4 feet 250

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 6 Month: 3 Year: 19 87

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3302' PBD 3302' Perfs at 2664-70'

1st plug pump 50 sx cement - stop at 2500',  
2nd plug pump 2 sx hulls, 10 sx gel, 50 sx cement, 5 sx gel, 1 sx hulls, release wiper  
plug and pump 120 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:45 p.m. Day: 6 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement with 1 sx hulls - stopped plug at 2070',  
2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 5 sx gel, 1 sx hulls and 120 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1500' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-20-87

INV. NO. 16358

Signed Paul Luthi (TECHNICIAN)

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas