

APR 28 1987

1 060954

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- N/A

SE NW SE, SEC. 16, T 28 S, R 13 W/E  
1650 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3055

Lease Name Swisher Well # 1

Operator: Petrie Exploration Company Inc.  
Name & Address Rt. 1  
Pratt, KS 67124

County Pratt 102.96

Well Total Depth 3168 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12:10 p.m. Day: 28 Month: 4 Year: 19 87

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3168' PBTD 3117' Perfs at 3071-78'

1st plug pump 25 sx cement with 1 sx hulls, stop plug at 2520',

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30 p.m. Day: 28 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 25sx cement with 1 sx hulls, stopped plug at 2520' - used common cement - Jack Luthi saw bottom plug,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement. Used 60/40 Pozmix 6% gel on top plug.

Maximum pressure 1000 psi and shut in 500 psi.

Remarks: Recovered 2039' of 4 1/2" casing. Used 60/40 Pozmix 6% gel and common cement by Allied. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-4-87

INV. NO. 16698

Signed Paul A. Luthi (TECHNICIAN)