

1041-413

TO: STATE CORPORATION COMMISSION

API NUMBER 15-151-20,823-00-00
SE SE SE SEC. 18, T 28 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MCGUIRE WELL # 1

TECHNICIAN'S PLUGGING REPORT 8/10

COUNTY PRATT 153.56

OPERATOR LICENSE # 5893

WELL TOTAL DEPTH 4725 FEET

OPERATOR: PRATT WELL SERVICE, INC. PRODUCTION CSG: SIZE 5 1/2" @ 4650' WITH 175 SX

NAME AND PO BOX 847 SURFACE CASING: SIZE 8 5/8" @ 214' WITH SX

ADDRESS PRATT, KS 67124 CASING LINER SIZE " W/ SX

RECEIVED
KANSAS CORPORATION COMMISSION

ABANDONED OIL WELL X GAS WELL INPUT WELL AUG 17 2000 SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PRATT WELL SERVICE, INC. WICHITA, KS LICENSE NUMBER 5893

ADDRESS PO BOX 847 PRATT, KS 67124

COMPANY TO PLUG AT: HOUR: 12:45 PM DAY: 10 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM TOM ROSE

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-2531

WERE: PERFS AT 4396-4402, 4080-4083. SQUEEZED PERFS 2896-2902 WITH 100 SX CEMENT.

SET CIBP @ 4037' AND PUT 2 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER. LOAD HOLE WITH

GEL. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 870' WITH 50 SX CEMENT. 2ND PLUG AT 250'

WITH 50 SX CEMENT. 3RD PLUG AT 60' WITH 15 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:45 PM DAY: 10 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT

SET CIBP @ 4037' AND PUT 2 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER. LOAD HOLE WITH

GEL. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 870' WITH 50 SX CEMENT. 2ND PLUG AT 250'

WITH 50 SX CEMENT. 3RD PLUG AT 60' WITH 15 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 1509' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED
DATE 8/22/00
2001060464

SIGNED Stephen J. Hunter (TECHNICIAN) FORM CP-2/3

Handwritten initials/signature