



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-077.30069-0000

RECEIVED
STATE CORPORATION COMMISSION

DEC -1 1965

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Paul Lacey of Beardmore Drilling Company has this date requested permission to plug the following described well:

Mr. Lacey guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drilling Company

Complete Address: 700 One Twenty Bldg., Wichita, Kansas

Lease Name: Anthony Well No. # 1

Location: NE SW Sec. 19 Twp. 31 Rge. 9 (E)(W) W

County Harper Total Depth 4638' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lacey was instructed to plug the well as follows:

242' of 8 5/8" surface pipe, cement circulated with 200 sacks.
Fill hole with drilling mud to 240', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacs.

Very truly yours,

Archie Elving
Conservation Division Agent