



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

15-077-30192-6000

DEC 17 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Harold Steincamp of Messman-Rinehart Oil Co has this date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Co.

Complete Address: 1432 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Darnes-Ison "C" Well No. # 1

Location: C NE NE Sec. 24 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 2965 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

189' of 8 5/8" surface pipe, cemented with 100 sacks.
Fill hole with drilling mud to 210', 1st cementing plug,
bridge with hulls, cement with 20 sacks. Fill hole with
drilling mud to 40', 2nd cementing plug, bridge with hulls,
cement with 8 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent