

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 17 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Norman Thompson of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: William Gruenerwald & Associates, Inc.

Complete Address: P. O. Box 909, Colorado Springs, Colorado

Lease Name: Fincham Unit Well No. # 1

Location: C N/2 N/2 NW Sec. 12 Twp. 28 Rge. 13 (E)(W) W

County Pratt Total Depth 4350' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

181' of 13 3/8" surface pipe, cement circulated with 320 sacks. 693' of 8 5/8" surface pipe, cement circulated with 450' sacks. Fill hole with drilling mud to 400', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent