

State of Kansas

FORM - CP-2  
Rev. 6-26-62

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 25 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Joe Gerritzen of Braden Drilling, Inc. has this  
date requested permission to plug the following described well:

Mr. Gerritzen guarantees payment of the plugging fee.

Operator's full Name: Braden Drilling, Inc.

Complete Address: 1620 Wichita Plaza, Wichita, Kansas

Lease Name: Devlin Well No. # 1

Location: C SW SE Sec. 11 Twp. 28 Rge. 13 (E) (W) W

County Pratt Total Depth 4455' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Gerritzen was instructed to plug the well as follows:

211' of 13 3/8" surface pipe, cement circulated with 300 sacks.  
766' of 8 5/8" surface pipe, cement circulated with 425 sacks. Fill  
hole with drilling mud to 300', 1st cementing plug, bridge with hulls  
and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd  
cementing plug, bridge with hulls and cement with 10 sacks to base  
of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving