

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY
Carol J. Larson, Executive Secretary

Governor
Chairman
Commissioner
Commissioner

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Towns of Mustang Drlg., Inc. has this date requested permission to plug the following described well:

Mr. Towns guarantees payment of the plugging fee.

Operator's full Name: Woolsey Pet., Corp.

Complete Address: 300 W. Douglas, Suite 400, Wichita, Ks. 67202

Lease Name: Buckner Well No. 2

Location: C NE SW Sec 9 Twp. 28s Rge. 13 (E)(W) W

County: Pratt Total Depth 3924 Oil Gas Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Towns was instructed to plug the well as follows:
389' 10 3/4" casing w/375 sax cement. 1058' 8 5/8" casing
w/180 sax cement. Pull 201' 8 5/8" casing. Set 50 sax plug
at 718'-Set bridge plug at 170' & fill to 10' below Gl. w/
70 sax cement. 5 sax in rat hole. Cemented by Allied.

Very truly yours,

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
JUL 30 1980
CONSERVATION DIVISION
Wichita, Kansas