

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

OCT 17 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name William Gruenerwald & Associates, Inc.
Complete Address: P. O. Box 909, Colorado Springs, Colorado
Lease Name Fincham Unit Well No. # 1
Location C N/2 N/2 NW Sec. 12 Twp. 28 Rge. 13 (X) (W) W
County Pratt Total Depth 4350'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Garvey Drilling Company
Address: R. R. # 2, Great Bend, Kansas License No.
Operation Completed: Hour 9:45AM Day 16th Month Oct. Year 1966

The Above well was plugged as follows:

181' of 13 3/8" surface pipe, cement circulated with 320 sacks. 693' of
8 5/8" surface pipe, cement circulated with 450 sacks. Hole was filled
with drilling mud to 400', 1st cementing plug, bridged with 2 sacks of
dry cement and 1/2 sack of hulls on fluid at 400', and cemented with 23
sacks. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40',
and cemented with 9 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/17/66

INV. NO. 4119-U