

15-151-30111-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Wm. Gruenerwald & Associates, Inc.

Complete Address: Box 909, Colorado Springs, Colorado

Lease Name R. Hodgin Well No. # 1

Location C SW NW Sec. 12 Twp. 28 Rge. 13 (E) (W) W

County Pratt Total Depth 4473'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No. _____

Operation Completed: Hour 9:45AM Day 18th Month July Year 1966

The Above well was plugged as follows:

.178' of 13 3/8" surface pipe, cement circulated with 325 sacks. 697' of 8 5/8"
surface pipe, cement circulated with 425 sacks. Hole was filled with drilling
mud to 400', 1st cementing plug, bridged with 1/2 sack of hulls on fluid at
400', and cemented with 25 sacks. Hole was filled with drilling mud to 40',
2nd cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cement-
ed with 10 sacks to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/19/66

INV. NO. 3584-u

Signed: Archie Elving
Well Plugging Supervisor