

KKANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Braden Drilling, Inc.

Complete Address: 1620 Wichita Plaza, Wichita, Kansas

Lease Name Devlin Well No. # 1

Location C SW SE Sec. 11 Twp. 28 Rge. 13 (E) (W) W

County Pratt Total Depth 4455'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Braden Drilling, Inc.

Address: 1620 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 5:30 PM Day 23rd Month Oct. Year 1965

The Above well was plugged as follows:

211' of 13 3/8" surface pipe, cement circulated with 300 sacks. 766'
of 8 5/8" surface pipe, cement circulated with 425 sacks. Hole was
filled with drilling mud to 300', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 300', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar, Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 10/26/65
INV. NO. 2037-W